Items of work	Per	Quantity	Rate	Cost	Total
Adding one vent to Bridge in 7 3/6 of Bangalore-Hindupur road.			Rs. a. p.		
1. Earthwork chargeable to road...					
2. Dismantling masonry work ...	C.ft.	778			
3. Concrete in surki mortar ...	„	191			
4. Brick in surki mortar ...	„	1,521			
5. Archwork in surki mortar ...	C.ft.	624			
6. Burnt stone slabs 4" thick dressed	Sq. ft.	81			
7. Plastering with surki mortar ...	Sqr.	10·72			
Mettalling and drainage etc., for diverting Bangalore Hindupur road from 2/35 to 2/36.					
1. Drainage... Earthwork excavation ..	C.yds.	5,882			
2. Mettalling complete ...	C.yd.	972			
3. Gravelling complete ...	„	1,459			
4. Sanding complete ...	„	324			
5. Removing and refixing furlong stones.	No.	7			
6. New furlong stone ...	„	1			
7. New tunnel stone ...	„	1			
Total ...	...	...	...	...	..
Total of all the works ...	...	...	...	...	...
Contingencies ...	...	...	...	...	...
Grand total ...	...	...	...	....	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Dated 12th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2nd February 1929, for constructing a Travellers' Bungalow and out-houses at Pavagada, Tumkur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3a. Percentage rates will not be accepted.

4. Each tender must be accompanied by a deposit of rupees four hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Travellers Bungalow and out-houses at Pavagada, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a Travellers' Bungalow and out houses at Pavagada, Tumkur District.

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
	Main Building.			Rs. a. p.	Rs. a. p.
1	Earth work excavation and filling ...	C.yd.	74		
2	Stone jelly concrete in mortar ...	C.ft.	529		
3	Burnt size stone in mortar ...	,,	1,738		
4	Burnt brick in mortar	,,	1,755		
5	Burnt stone slabs 6" thick exposed portions dressed and fixed.	S.ft.	294		
6	Cut stone pillars 7" x 7" nicely dressed including base and capital, etc., complete.	Each	6		
7	Do half pillars	,,	4		
8	Teak-wood doors with panelled shutters double including iron fittings iron clamps, etc., complete as per marriet specification silicate chacolately painted.	S.ft.	179		
9	Teak-wood door with battened shutters iron fittings iron clamps, etc., complete including silicate painting.	,,	28		
10	Teak-wood windows with panelled shutters outside and glazed shutters inside with iron bars $\frac{3}{4}$" dia. iron fittings iron clamps with silicate chocolating (included) as per marriyets specification.	,,	72		
11	Teak-wood windows with battened shutters $\frac{3}{4}$" iron bars, iron fittings iron clamps, etc., complete including chocolate painting as per marriyets specification.	,,	18		
12	Teak-wood work wrought and put up including wood oiling.	C.ft.	110·05		
13	Rolled steel joists of English section including painting and hoisting.	Cwt.	$5\frac{1}{3}$		
14	Roofing with pucca terrace one course of brick on edge and three course of flat tiles on mortar with brick jelly concrete and plastering both sides complete.	Sqr.	7·41		
15	Roofing with 1st class Tumkur tiles Mangalore pattern on teak reepers 2" x 1" the eave tiles being tied up by a teak bottom screw down to rafters.	,,	4·48		
16	Ridge tiles set in mortar and cement pointing.	R.ft.	26		
17	Teak-wook eave board ornamental including painting.	,,	56		
18	Chunam plastering	Sqr.	34·23		
19	Flooring with $1\frac{1}{2}$" thick cudappa slabs on stone jelly chunam concrete 3" thick and cement pointing complete.	,,	2·28		
20	Flooring with 1st class Tumkur tiles Mangalore pattern on 3" stone jelly chunam concrete bed and cement pointing complete.	,,	5·85		
21	White and colour washing 2 coats ...	,,	34·23		
22	Chunam pointing	,,	2·80		
23	Burnt brick in chunam parapet wall with ornamental cornice.	R.ft.	152		
24	Teak-wood glazed ventilators ...	S.ft.	4		
25	Constructing cisterns and clearing site ...	Lump	sum		
	Vegetarian kitchen.				
1	Earth work excavation and filling ...	C.yds.	16		
2	Burnt size stone in clay	C.ft.	567		
3	Burnt brick in mortar	,,	197		
4	Do in clay	,,	821		
5	Burnt stone slabs 6" thick exposed portion dressed and fixed.	S.ft.	118		

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
6	Teakwood battened door	S.ft.	101	Rs. a. p.	Rs. a. p.
7	Teakwood windows with battened shutters, iron bars ¾" dia, iron fittings iron clamps, etc., complete.	,,	9		
8	Teakwood work wrought and put up including wood oiling.	C.ft.	37·70		
9	Roofing with First Class Tumkur tiles Mangalore pattern on teak reepers 2" × 1" the eave tiles being tied up by a teak batten screw down to rafters.	Sqr.	7·40		
10	Ridge tiles set in mortar and cement pointing.	R.ft.	29		
11	Teakwood eave board ornamental including painting.	,,	110		
12	Chunam plastering	Sqr.	19·65		
13	Flooring with 1½" thick Cudappah slabs on stone jelly chunam concrete 3" thick cement pointing, etc., complete.	,,	2·93		
14	Burnt brick in mortar arch work ..	C.ft.	10		
15	White and colour washing 2 coats ...	Sqr.	19·65		
16	Chunam borders	R.ft.	42		
17	Chunam pointing	Sqr.	1·27		
18	Ventilating tiles	Each	4		
19	Providing stone pestal and mortar ...	Lump	sum		
20	Teakwood glazed ventilators with iron bar, iron works, etc., complete.	S.ft.	22		
21	Constructing cisterns and clearing site.	Lump	sum		
	Out Houses.				
1	Earthwork excavation and filling ...	C.yd.	17		
2	Burnt size stone in clay	C.ft.	677		
3	Burnt brick in mortar	,,	390		
4	Do clay	,,	894		
5	Burnt stone slabs 6" thick exposed portion dressed and fixed.	S.ft.	33		
6	Teakwood battened door with iron fittings, etc. complete.	,,	18		
7	Teakwood windows with battened shutters ¾" iron bars, iron fittings, iron clamps, etc., complete.	,,	9		
8	Teakwood work wrought and put up including wood oiling.	C.ft.	41·96		
9	Roofing with First Class Tumkur tiles Mangalore pattern on teak reepers 2"× 1" the eave tiles being tied up by a teak batten screw down to rafters ...	Sqr.	7·60		
10	Ridge tiles set in mortar etc. ...	R.ft.	40		
11	Chunam plastering	Sqr.	19·37		
12	Burnt brick in mortar arch work ...	C.ft.	46		
13	White and colour washing 2 coats ..	Sqr.	19·37		
14	Pointing with chunam	,,	1·00		
15	Constructing cisterns and clearing site ...	Lump.	sum		
16	Gravel flooring	Lump	sum		
	Constructing Latrine	Lump	sum		

V. V. PATANKAR,
Executive Engineer.